

BANGALORE DIVISION.

Notification dated 9th March 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 1st April 1940, for restoring and improving Sivanahalli Hutchappanakere, Reg. No. 146 of Closepet Taluk.

2. Tenders in the prescribed form obtainable on payment of Re. 0-4-0 per form from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for Restoring and Improving Sivanahalli Hutchappanakere Tank, Reg. No. 146 of Closepet Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan for having credited into the Treasury the deposit amount of Rs. 245 under 17 (a) P. W. Deposits or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 1st April 1940 at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 3 for each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department Schedule of Rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of December 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 1-8-0 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(a) The contractor should at his own cost—

- (1) Provide rods, stakes, ropes and labour required in setting out the works.
- (2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
- (3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
- (4) Arrange for protecting work during inclement weather.
- (5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parabs, shoring, strutting and other requisite protective appliances during the progress of the work.
- (6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
- (7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
- (8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
- (9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
- (10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(b) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities for restoring and improving Sivanahalli Hutchappanakere Tank, Register No. 146, Closepet Taluk.

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Figures	Words
	<i>I. Raising the bund to R. L. 56.00 with a top width of 4½ feet.</i>		Rs. a. p.		Rs.	Rs.
1	Clearing jungle with roots	Grade	1 0 0	21		
2	Removing ant hills and filling with sand	Each	1 0 0	3		
3	Cutting grips in front and rear steps	Grade	1 8 0	21		
4	Earthwork to bund with watering and tamping including required lead and lift	C.yd.	0 3 0	2,509		
5	Turfing the front and rear slopes and watering till it is satisfactory	S.yd.	0 0 9	4,417		
6	Rough stone revetment new, with jelly backing and jelly wedging including required lead and lift, etc., complete	C.yd.	1 4 0	840		
7	Rough stone revetment old with new jelly backing and jelly wedging including removing and resetting lead and lift, etc., complete	"	0 10 0	489		
8	Providing and fixing grade stones with bed slab in concrete including figuring and painting	Each	1 8 0	21		
9	Providing and fixing Index stones	"	0 6 0	21		
10	Do do B.M. stones in concrete including figuring and painting	"	2 8 0	2		
11	Providing and fixing gauge stones on a bed slab including figuring and painting, etc.	"	14 0 0	1		
12	Providing and fixing Register Number stone on a bed slab including figuring and painting	"	2 8 0	1		

No.	Item of works	Unit	Rate	Quantity	Rate to be quoted in	
					Figures	Words
	<i>II. Cast Iron Pipe Sluice at R. L. 45.00.</i>		Rs. a. p.		Rs.	Rs.
1	Earthwork excavating foundation cut opening the bund and refilling with watering and consolidation	C.yd.	0 5 0	118		
2	Stone jelly concrete in cement mortar 1 : 5 : 10	C.ft.	0 5 0	206		
3	Burnt stone slabs 6" thick dressed and fixed in cement mortar	S.ft.	0 6 0	48		
4	Burnt size stone in cement mortar 1 : 6	C.ft.	0 5 6	298		
5	Cutting holes in the slabs	Each	0 8 0	5		
6	Pointing with cement mortar 1 : 3	Sqr.	3 8 0	3.08		
7	Plastering with cement mortar 1 : 3	"	8 0 0	0.32		
8	Providing and fixing jelly wood plug and iron rod with locking arrangement, etc., complete	Each	12 0 0	1		
9	Providing, carting and fixing cast iron pipe 6" dia. including jointing, etc., complete	R.ft.	2 10 0	30		
	<i>III. Masonry Waste Weir R. L. 51.00 (130 feet long).</i>					
1	Earthwork excavation for foundation for the bodywall	C.yd.	0 3 0	547		
2	Stone jelly concrete in cement mortar 1 : 5 : 10	C.ft.	0 5 0	1,380		
3	Size stone in cement mortar 1 : 6 including cement pointing	C.ft.	0 5 6	2,624		
4	Providing cement concrete 1 : 2½ : 5 for coping slab including cement plastering 1 : 3, etc., complete	C.ft.	0 10 0	56		
5	Providing new rough stone revetment with jelly backing and jelly wedging with required lead and lift	C.yd.	1 4 0	320		
6	Rough stone revetment old with new jelly backing and jelly wedging including required lead and lift	C.yd.	0 10 0	166		

N. LAKSHMINARASIMHAIA,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 5th March 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 p.m. on 16th March 1940, for the work of construction of masonry anes across Enne Hole and installing automatic syphons at Mudigere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 225 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for the work of construction of masonry anes across Enne Hole and installing automatic syphons at Mudigere Taluk," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.